Lean & Sustainability in the Alliance

Lean in the Public Sector Nottingham Trent University 19&20 September 2013





Anglian Water

Our region stretches from the Humber north of Grimsby, to the Thames estuary and then from Buckinghamshire to Lowestoft on the east coast.

Our 80,000 km of water and wastewater pipes could take us a quarter of the way to the moon! They supply and transport water across an area of 27,500 square km.

We're the largest water and wastewater company in England and Wales by geographic area.









The @one alliance



The @one Alliance is a collaborative organisation comprising client, design consultants and contractors, formed to deliver a large part of the Anglian Water AMP4 & AMP5 capital investment programme



AMP5 Initiatives

Initiative	Opportunities
Commercial and Overhead	 Single bank account AMP5 contracts Cost assurance Owner controlled insurance
Common Delivery Process	 Project Definition Application of gateways Allocation to delivery routes
Product-based Delivery	 Development of standardised products Integrated Sustainability in Design team
Supply Chain	Common frameworksPerformance management
Risk and Value	 Application of R&V across whole programme Enhancement of the R&V process Enhancement of the root cause analysis tool
Waste	 Reliability of task completion Rework Materials waste



Corporate Responsibility & Sustainability

@one

CR&S

Sustainability in construction: to be recognised as leaders in the industry through empowering all sites to deliver sustainable construction

Sustainability in design: to have demonstrable benefits from adopting sustainable design across all projects and standard products

Financial performance: to have decision making processes representing a leading model for a sustainable business

Supply chain: to have an ongoing engagement with our supply chain in providing sustainable products and services

Local communities/Customer satisfaction: to be working in partnership with local communities



WAST

Waste: to have lean principles embedded as normal practice to eliminate all forms of waste

> **Ecology and environment**: to have zero environmental incidents and an environmental strategy aligned to Anglian Water Services

Health and safety: to have a common and industry leading H&S culture

Training and education: to be recognised as a leader in the development of leadership, change management and improvement in the construction sector



AMP5 Initiatives

Waste Initiative: to have lean principles embedded as normal practice to eliminate all forms of waste

	The 8 Lean Wastes	@one Alliance equivalent			
1	Overproduction				
2	Overprocessing				
3	Waiting	Delichility of tools completion			
4	Unnecessary Motion	Reliability of task completion			
5	Unnecessary Transport				
6	Underutilisation of Skills				
7	Defects	Rework			
8	Inventory	Materials Waste			



Changing the Alliance culture



Changing the way we think about waste & sustainability...

We are making **waste & sustainability** visible and challenging teams to reduce all aspects of **waste** and improve all aspects of **sustainability**...

Making **waste & sustainability** visible has enabled us to make decisions about which process improvements to work on first...

Lean and Sustainability

To inspire joined up thinking, we illustrate the link between **lean construction** and **sustainability**...





The links between Lean construction and sustainability (adapted from Shepherd Construction)

Reliability

Doing what we said we were going to do, when we said we were going to do it

Collaborative Planning



What are we planning to do?

> planned tasks what / who / when



Production Meetings



Did we achieve what we were planning to do?

> actual tasks completed
compared to planned tasks

Reliability Reporting

		Planned Weeks Progress							@one	
Contract Name han Park Eskte TPS - Rising) SEW Number SEM-08206 Barhale C No. AR0065		Site Agent Week Commencing		Stuart Kenpster 21-Mar-11				Clear contents Re-size E-mail to @one Malbox		
TACK	Reporting	21-Mar	22-Mar	23-Mar	24-Mar	25-Mar	26-Mar	27-Mer	Actual Duration (for this week)	
IAJA		Man	Tue	Wed	Thu	Fri	Set	Sun		
Connection drill	Planned Task							1	5000	
shots together	Task complete as Planned	W#		No						
	Causal Factor			o refer	of Task Underestingted					
Test Rising Main	Planned Task							(reproprieted for Non-201	
	Task complete as Planned				No					
	Causal Factor				Dame	of Tesk U	detertion	使线		
Test Water pipe	Planned Task							li and	revolution for Lection	
	Task complete as Planned					No		Ú.		
	Causal Factor					(and the	of Task U	nderestin		
	Planned Task							lí i		
	Task complete as Planned	_						ų		
	Causal Factor									

What stopped us doing what we planned to do?

- > identify blockers
- > use data for process improvements

Rework

During the Construction Phase, we measure Rework using the Punchlist...



<u>oone</u>

Designing out Waste and Carbon

Driving the zero waste to landfill and lower carbon ethos by working with the design teams to reduce the amount of waste and carbon we produce...



Embedding Waste Reduction through Sustainability

We have developed a number of process and toolkits to enable our designers to consider carbon and waste at the outset of their designs...



Sustainability hierarchy

Our design engineers use a four-stage process to remove embodied carbon and waste at the project planning stage.





Best practice examples



Drop in sessions

Product-based delivery – Standard Products

A product is a standard unit of asset delivery which delivers more value the more times it is used

- initiative developed to drive efficiencies within our delivery programme
- move away from bespoke designs to standard modular solutions
- through the use of Standard Products we reduce redesign, rework and waste...
- which in turn minimises design time, project expenditure and construction programme

design the product once get it right use it many times...



Product-based delivery – Standard Products & Build Offsite

Wastewater UV channels

- Traditionally concrete channels constructed on site
- Worked with suppliers to develop an offsite modular UV channel
- Full testing in the factory plug and play
- Reduced construction time from 16 to 8 weeks
- Removes the need for kiosk for control panel; no requirement for planning permission





ABIC FL





Product-based delivery – Standard Products & Build Offsite

Chlorination Standard Product

- New Standard Product manufactured and tested offsite reducing on-site construction activities
- Assured visual appearance and right first time build quality
- Large reduction in material waste and embodied carbon
- Health and safety risks reduced due to less work on site
- Savings currently being quantified but expected to be greater than 20%









Product-based delivery – Standard Products & Build Offsite

Water Treatment Works

Booster station assembled and tested in the factory, delivered to site and craned into place for final connections to be made









Materials Management

Driving the Zero Waste to Landfill ethos by working with the construction teams to use improved waste management techniques to deal with the waste we create



■ REDUCE ■ REUSE on site ■ REUSE offsite ■ RECYCLE ■ RECOVER ■ DISPOSE to Landfill



In summary...

In AMP5, between April 2010 and June 2013:

- 30% estimated reduction in waste production
- over 260,000 tonnes waste diverted from landfill
- increase in waste diverted from landfill from 72% to 98%
- increase in reuse of material from 32% to 46%
- 34% reduction in embodied carbon and 80% reduction in operational carbon
- no infringements on protected species and one category 3 pollution incident
- Accident Frequency Rate equal to 0.11
- ongoing engagement with our top 50 suppliers on health & safety, sustainability, carbon management, waste reduction, and environmental issues
- supply chain included in health & safety and environmental training
- more than 90% of our workforce recruited from the East of England and almost 60% of our expenditure spent with local suppliers
- more than 20% reduction on expenditure compared to the business plan forecast

