# **TEHRAN METRO LINE#6**

# **Improvement of Production and Quality**

# **Through Lean Methods and Cooperation**

# With The Public Client


Homayoon Orumchi Manager of Eng. Department AHAB Co. <u>h - o r u m c h i @ a h a b c o . c o m</u>




# **AHAB Company Profile**

### Engineering and Construction of Infrastructures: Dams, Tunnels, Pipe Lines, Irrigation Plants,...







### General terms learned:

- ✓ Poka yoke
- ✓ Mistake proof
- 🥖 6 sigma
- √ 5S
- ✓ Design for production
- Lean production

### Master minds:

- Glenn Ballard, PhD
- Gregory Howell, P.E....

participants of the tunneling project who attended in workshop: *Client: Tehran metro EPC Contractor: AHAB Co. MC: Behro* 

# <u>Tehran workshop</u>

**Teheran Sept. 27 - 29, 2010** By Prof. Dr. – Ing. Fritz Gehbauer. M.S

participants of the workshop:

Client: TEHRAN URBAN AND SUBURBAN

RAILWAY COMPANY (METRO)

**MC:** TEHRAN BEHRO CONSULTING ENGINEERS

**EPC CONTRACTOR OF TUNNELING OF** 

PHASE ONE: AHAB CO.

Main concepts of seminar: What is Lean? **\*** factors which are hindering project work The Last Planner System (LPS) of Project **Planning and Control** \* New forms of cooperation Alliancing, Team building **\*** The Big Room


# **Tehran workshop**



1 MC

Group work on the planning of tunneling project phases





### New and Successful Approach to

# Collaborative

# Planning


### With The

Public Client, Consultants and the Contractor




# **MECHANIZED TUNNELING TBM PROJECT**

# **Tehran Metro Map**



### Introduction



South Part of the Project: Tunneling Line 6 of Tehran Metro by Mechanized TBM Machine


# **Tunneling Contract**



With a TBM and very Limited Space at the **Tunnel Face Just In Time** ls a Must...!



VSM Value Stream Mapping of Mechanized Tunneling In Tehran Metro Line # 6



### **HOW WAS THIS ACHIEVED...?**


Lean construction concepts and means were applied

for control of the TBM operation to identify the


amount and the extent of the effective

uncertainties. It was enhanced by using turtle

diagrams & cause and effect diagram









3- With what ? (Equipment/Facility)	Comments		
TBM	Diameter of cutter head 9.15 m		
Conveyor	To transporting soil out of the tunnel		
Power plant	5 MW power plant for TBM		
Water			
Rail	Due to moving TBM		
	lifting segments from MSV and put them on		
Vacuum lifting device	feeder		
segment feeder	Transporting segments to erector		
Erector	Installing Segments on the tunnel wall		

5- With who ? (From training records)	Requirement	Number(s) (2 shifts)
TBM Supervisor	mechanic engineer	1
TBM operator	Trained operator	1
Electrical supervisor	Electronic engineer	1
Power plant controler	Electronic engineer	4
TBM serviceman	Skilled Labour	2
H&E (conveyor belt)	Skilled Labour	2
Welder	Labour	2
Erector operator	Mechanic technician	2
Segment feeder operator	Mechanic technician	2
Grout responsible	Skilled Labour	2
Mechanical part responsible	Mechanic engineer	2
PLC man	Electronic engineer	1
VMT responsible	surveyor	1
Installing air duct responsible	Skilled Labour	1
Cleaner	Labour	3
	Sum	27

2- Inputs (Information/process)	Comments		
Alignment design	AHAB		
Tunnel diameter	9.15 m		
Average of advancing	15 m/day (10 rings/day)		
excavation capacity	24 m/day (16 rings/day)		
Length of the tunnel	11700 m		
Field geotechnical investigation	АНАВ		
Face pressure	Gueno consulting engineers		
key position	in accordance with path direction		
VMT			
Required grout rate in a ring	8 m3 / ring		

1- Process name	
Tunnel M	Aining
Advance rate	1.5 m (1 ring)
Excavating duration	35-45 min
<b>Ring Installing Duration</b>	25-35 min
Process before	Process after
Segment production	Ring Installation
Steel Cage Production	Muck out
Transporting Grout,	Waste Water
Foam, Grease,	



10.0


	7- Outputs (Product/Process)	omments
Advanced (r	Advanced (m/day)	Prepared for ring
	Advanced (myday)	installation
	Number of built rings per day	2 shifts

	~
4- How ?	Requirement/
(From flow chart )	who provides?
TBM Excavating instruction	Herrenknecht Co.
Rail installation	Rail
Adding conveyor belt (each 250 m)	Conveyor belt
Water Supply instraction	
electrification instruction	cable,hook bolt
feeder charging instruction	Herrenknecht Co.
Grout injection instruction	
installing & adding air duct	




6- Performance (Process standard & measurement)	mments
Efficiency	Advance rate (meter/month)
Daily Excavation	Meter
Deviation rate	Conflict with designed direction
VMT Reporst	
Excavation standard	OSHA

<u>By:</u>




**COMPARISON OF TUNNELING CONSTRUCTION PROJECTS IN TEHRAN** 





### Segment Plant and innovation



The segment factory is designed for 9 sets which form 9 complete rings...

Through VSM and Lean Manufacturing Methods:

**\*ENERGY SAVING \*REDUCED INVENTORY \*INCREASE QUALITY**

st ....

### **Production of The work begins by de-molding the previous day or shift production, all segments one by one** Other activities are added to complete the process

### Work Flow 1

7:00-7:05 7:05-7:10 7:10-7:13 7.12-7.18 10:38-10:42 10:42-10:46 Sta 1<sup>st</sup> Mou Las Cu Ea 1<sup>st</sup> Ear last Opening Mould -5 min (1)Putting Reinforcement inside the mould -3 min Picking up the segment -5 min Concreting -4min Cleaning and Oiling -5min Smoothing -4min

Dayshift		
art	7:00	Start
<sup>t</sup> Concreting	10:38	1 <sup>st</sup> Concreting
st Concreting	14:30	Last Concreting
iring during	10 hrs.	Curing during
rliest de-molding time for <sup>t</sup> concreting	20:38	Earliest de-molo 1 <sup>st</sup> concreting
rliest de-molding time for st concreting	00:38	Earliest de-mole last concreting


Nightshift	
Start	20:38
1 <sup>st</sup> Concreting	00:38
Last Concreting	4:38
Curing during	10 hrs.
Earliest de-molding time for 1 <sup>st</sup> concreting	10:38 (Next day)*
Earliest de-molding time for last concreting	14:38
_	

Nightchift

This means: that day shift can't start working at 7:00 am on next day!

### designed to consider the importance of curing duration required and also in order to place plant facilities

### Work Flow 2



Dayshift		Nightshift		
Start	7:00	Start	19:00	
1 <sup>st</sup> Concreting	7:33	1 <sup>st</sup> Concreting	19:33	
Last Concreting	17:00	Last Concreting	5:06	
Curing during	10 hrs.	Curing during	10 hrs.	
Earliest de-molding	17.22	Earliest de-molding	5:33	
time for 1 <sup>st</sup> concreting	17:33	time for 1 <sup>st</sup> concreting	(Next day)	
Earliest de-molding	2.00	Earliest de-molding	15.06	
time for last concreting	3:00	time for last concreting	15:06	

For creating the possibility of a two full cycle production with the cheapest curing system, the work flow 2 is the only chance

### **Segment Damages During Construction**

Damaged category	Crack in axial 	Crack in circumferential direction	Chipping at segment corner	Stripping around segment	Stripping around ring joint	Hair crack at inner surface	Stripping around erector guide	Others
Segment damaged	13	11	78	54	68	0	140	14
Total number of segment checked	9000	9000	9000	9000	9000	9000	9000	9000

# Comparing These Results With Sugimoto, 2006, Shows The High Quality Of Segments During The Construction Tunnel In Tehran Metro Line#6


### A Special Form of Cooperation With The Public Client

Second Part Of The Contract With The Price Of 100 Million Dollars Which Consist Of Building 13 Stations .


Financial resources of project is supported by a barter treaty which entitled "Sadr Complex". It defines AHAB company as a investor on Engineering, Procurement and Construction of 9 stations in line # 6 and 4 stations in other lines.(1,2 &3)




### Through Visions and Dreams to Reality of Leadership and Lean on Tehran Metro Line #6



### **Tunneling and Stations an Integrated Project**




### **PROBLEMS DURING CONSTRUCTION**




# LAST PLANNER

		M J J A SOND J F M A M J J A SOND J F M A M J J A SON
🕾 🖻 Tehran Metro Line 6 South Part	471.38 d	φ
Primary site mobilization	45 d	
Site land handover	0 d	♦ 1605
Fixing requrement permission	30 d	d d
Resolve conflict	30 d	ď
Commencing site mobilization	30 d	<b>b</b> _
Construction of Ramp & Access gallery	153 d	
Construction of the ramp	35 d	
Construction pile & inserting H-pile & concreting	30 d	<u>è</u>
Trench digging	25 d	<u>∞</u>
Construction of the tunnel gate	20 d	<b>L</b>
Construction of the tunnel gate structure	3 d	<u>й</u>
Construction of the access gallery	120 d	
Excavation of the access gallery	60 d	
Shotcrete of the tunnel wall	60 d	-
9 Lighting	60 d	
Excavation (ticket hall to plarform)	60 d	, <b>b</b>
access gallery stabilization (ticket hall to plarform)	60 d	i i i i i i i i i i i i i i i i i i i
lighting (ticket hall to plarform)	60 d	
Access Construction	30 d	
Excavation	30 d	•
excavation & bar bending & concreting	10 d	1
Access gallery	10 d	1
Middlle main gallery	60 d	9








**Category of variance** 15 14 13 12 11 10 9 8 Category of 7 6 variance 5 4 3 2 1 0 Scheduling Coordin. Engineering Design Approvalel Permits owner decision Prefectibile work Contractes CO'S Subnittals Site Conditions Fauipment Materials REFIS 1.300r 4 3 ----Prerequisite work -Engineering/ Design ------Materials 2 ----- Prerequisite work 1 ----labor 0 week 2 week 3 week 4 week 5 week 1 week 6

High underground water level caused serious problems in construction of station. And, one of the most important causes of variances is inapplicable design.

# **Tunnel and Station Construction**



### What Has Been Achieved...?



Contradiction of the values in project pieces

**Resolved by INTEGRATION** 

# NOW, WE HAVE TRANSPARENCY MUCH MORE THAN BEFORE

(We Had It But Not This Much)



# **SUMMARY**

